

PROPOSAL

To: Tony Edwards

Date: Jan. 10, 2010

Phone:

Fax:

From: Vess Excavating Ltd.
2330 Commonwealth Drive
Charlottesville, VA 22901

Project: **Belmont Bridge East Sidewalk Replace**

As requested, the following is proposed:

DESCRIPTION

- Mobilize to include traffic control (arrow board and traffic barrels to redirect traffic)
- Place form and protection under the bridge (using the diaphragms as supports)
- Cut the sidewalk at the face and a step pattern over "Beam J"
- Demo the concrete
- Drill for dowelling (at both cut locations), new steel reinforcing (#4 bar, 1ft on centers)
- Form
- Pour new concrete walk to match existing in thickness

Total Job ----- \$ 336,548.00

Exclusions:

- Permits, Bonds, Fees of any kind.
- Buried or overhead utilities, Relocation, Repair, or Replace.
- Quantities obtained from site visit by Vess Excavating Ltd.. Should change in scope discussed occur, price will be adjusted accordingly.
- Any engineering including lay out, testing or any other acts associated with this field.
- Price does not include stake out or any other controls.
- Asphalt repair unless damaged by Vess Excavating, Ltd.
- Railroad Insurance or bonding. Any fees associated with Railroad.
- Everything not included in Vess Excavating Ltd.'s Scope of work**

Brian A. George
Vess Excavating Ltd.